KETUA BAHAGIAN KEJURUTERAAN
MARKAS OPERASI
PASUKAN POLIS MARIN SANDAKAN
WILAYAH EMPAT (4) SABAH
POLIS DIRAJA MALAYSIA
JALAN BULI SIM-SIM
90000 SANDAKAN, SABAH

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
	Boat Specifications:					
	Nama / No bot : RHIB 47 PPM SEMPORNA					
	Jenis Hull : Fibreglass					
	Length overall : 12.45 Meter					
	Beam overall : 2.98 Meter					
	Draft : 0.58 Meter					
	Weight : 4.0 Ton					
	Speed : 45 Knot					
	Enjin : YAMAHA V8 350HP - 2 Units					
	Engine R/Hours : Port - 1400 Hrs					
	: Stbd - 3200 Hrs					
	Engine Serial No : Port - 6 AXU 1007030					
	: Stbd - 6 AWX 1008332					
	Fuel tank : 1000 Liter					
1	**SLIPPING AND UNSLIPPING**					
1.1	To docking and undocking boat.					
	RM x	2.1				
1.2	Docking chargers 30 days.					
	RM x x	2.2				
1.3	Crane charges to lift up bot from trailer to cradle & from cradle to trailer after completion of work.					
	RM x	4.7.2				
2	**UNDERWATER HULL (22.66m²)**					
2.1	To scrape marine growth,wash down and clean underwater hull with HP freshwater (22.66m²)					
	RM x m2	3.3				
2.2	Labour to grinding underwater hull to bare fibre. (22.66m²)					
	RM x m2	3.6(a)				
2.3	Labour and material to rebuilt powder at underwater hull pitted area.					
	RM x mh	41				
	Material;					
a	Powder fibreglass - 0.5 kg					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
2.4	Labour to grinding underwater hull to smooth before painting. (min. charge 10m²)					
	RM x m2	3.6(a)				
2.5	To wash down after grinding and before painting underwater hull area.(22.66m2)					
	RM x m2	3.2				
2.6	Labour to paint the whole underwater hull according to specification layer coats by conventional spray method.(22.66m²) (4 coat)					
	RM x x m2	3.13(a)				
	Material;					
a	Hemple paint undercoat red 5liter - 2 tin					
	RM x x	42				
b	Hempadur Quattro - 2 tin					
	RM x x	42				
c	Hemple paint yellowish 5liter - 2 tin					
	RM x x	42				
d	Hemple paint black Antifouling 5liter - 2 tin					
	RM x x	42				
e	Hemple thinner 08080 - 2 tin					
	RM x x	42				
2.7	Labour to reposition chock/block to complete coverage painting.					
	RM x block	2.4				
3	**SHIPSIDES PORT AND STBD (14.24m²)**					
3.1	Light scrape and throughly clean shipside hull and transom with HP freshwater (14.24m²)					
	RM x m2	3.3				
3.2	To grinding the whole ship side area to sound paint. (14.24m²)					
	RM x m2	3.6(a)				
3.3	Labour and material to rebuilt cement putty at shipside area.					
	RM x mh	41				
	Material;					
a	Cement putty - 0.5 tin					
	RM x x	42				
3.4	Labour to grinding shipside to smooth before painting. (min. charge 10m²)					
	RM x m2	3.6(a)				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
3.5	To wash down after grinding and before painting shipside area. (14.24m²)					
	RM x m2	3.2				
3.6	Labour and material to paint shipside and bracket 2 coat paint by spray. (14.24m²)					
	RM x x m2	3.13(a)				
	Material;					
a	Hemple paint black color - 1 tin					
	RM x x	42				
b	Hempel Thinner - 0.5 tin					
	RM x x	42				
4	**TRANSOM (2m²) AND MOTOR WELL (4m²)**					
4.1	Fresh water clean transom and motor well (min.charge 10m²)					
	RM x m2	3.2				
4.2	Labour and material to cutting motor well to give way renewal transom.					
	RM x mh	41				
	Material;					
a	Fibreglass mat - 40kg					
	RM x x	42				
b	Fibreglass resin - 80kg					
	RM x x	42				
c	Hardener - 0.8kg					
	RM x x	42				
d	W/proof plywood 12mm - 6 sheet					
	RM x sheet	8.9.2				
4.3	To grinding the whole transom and motorwell area to sound paint. (min.charge 10m²)					
	RM x m2	3.6(a)				
	Material;					
a	Simen putty - 1 kg					
	RM x x	42				
4.4	Cleaning the transom and motor well with HP fresh water before painting. (min.charge 10m²)					
	RM x m2	3.2				
4.5	Labour and material to spray paint transom (min.charge 10m²)(4 coats)					
	RM x x coat	3.13(a)				
	Material :					
a	Hempadur Red - 1 liter					
	RM x x	42				
b	Hempadur Quattro - 1 liter					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
c	Hempadur Yellowish - 1 liter					
	RM x x	42				
d	Black Antifouling - 1 liter					
	RM x x	42				
e	Hempel Thinner - 0.5 liter					
	RM x x	42				
4.6	Labour and material to respray paint motor well (min.charge 10m²)(2 coats)					
	RM x x	3.13(a)				
	Material :					
a	Hempathene Black - 2 liter					
	RM x x	42				
b	Hempel Thinner - 0.5 liter					
	RM x x	42				
4.7	Labour and material to remove, renew and reinstall outlet drain canvas .					
	RM x mh	41				
	Material :					
a	Canvas - 2 pcs					
	RM x x	42				
4.8	Labour and material to remove, renew and reinstall inspection cover motor well.					
	RM x mh	41				
	Material :					
a	Deck Inspection Hatch 353mm X 606mm - 1 unit					
	RM x x	42				
b	Deck Inspection Hatch round dia 8" - 2 sets					
	RM x x	42				
5	**POLYURETHANE FENDERS PORT AND STBD**					
5.1	Labour and material to repair fender port and stbd.					
	RM x mh	41				
	Material;					
a.	Hyphalon cloth 1.5mm - 26m					
	RM x x	42				
b.	Rima Tic SC 2000 - 20 kg					
	RM x x	42				
c.	Harderner UT-R 20 40 gram - 20 tin					
	RM x x	42				
d.	Repair kit Flex - 10 set					
	RM x x	42				
e.	Pentens 609 flex sauges - 25 tubes					
	RM x x	42				
f.	SST Stud Bolt and Nut 3/4" x 10" - 50 Sets					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
5.2	Labour and material to repair bracket fibreglass below fenders					
	RM x mh	41				
	Material;					
a.	W/P plywood 12mm - 2 sheets					
	RM x sheet	8.9.2				
b.	3mm (T) x 25mm Aluminium Flat Bars - 20 Meters					
	RM x mtr	5.3.4				
c.	Fibreglass mat - 15 kgs					
	RM x x	42				
d.	Resin - 30 kgs					
	RM x x	42				
e.	Hardener - 0.5 kg					
	RM x x	42				
f.	S/S Tapping Screw 1/2" x 1 1/2" - 120 Sets					
	RM x x	42				
6	**MAIN DECK, BOW DECK AND CONSOLE PANEL (18m²)**					
6.1	Labour and materials to grinding smooth main deck surface in order for paint application. (18m²)					
	RM x m2	3.6(a)				
6.2	Labour and material to rebuilt cement putty console panel, storage box, passengger seat, pilot seat and surrounding main deck.					
	RM x mh	41				
	Material:					
a	Simen putty - 1 kg					
	RM x x	42				
6.3	Labour to grinding main deck, floorboard, console panel, passenger seat, pilot seat, and storage box to smooth before painting. (min.charge 10m²)					
	RM x m2	3.6(a)				
6.4	Fresh water cleaning before painting. (18m²)					
	RM x	3.2				
6.5	To repaint whole console panel, top side and main deck of the boat with finish coat black. (18m²)(2 coats)					
	RM x x coat	3.13(a)				
	Material;					
a	Hemple paint undercoat 5 liter - 2 tin					
	RM x x	42				
b	Hemple paint black color 5 liter - 2 tin					
	RM x x	42				
c	Hemple thinner 08080 - 0.5 tin					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
d	Anti Slint - 2 bags					
	RM x x	42				
6.6	Labour and material to remove, renew and refit cushion cover pilot seat, OOW, gun man and passenger seat.					
	RM x mh	41				
	Material:					
a	Super leather cover Pilot and OOW - 2 sets					
	RM x x	42				
b	Super leather cover Passengger 40" x 10" -4 sets					
	RM x x	42				
c	Super leather cover Gun man - 1 sets					
	RM x x	42				
d	Super leather cover long bench 62"x38" -1 sets					
	RM x x	42				
e	SST bolt and nut 1/4" x 2" - 42 Sets					
	RM x x	42				
6.8	Labour and material to remove, service and reinstall bollard and bracket after deck and forward deck					
	RM x mh	41				
	Material :					
a	SST plate 3mm 4" x 8" - 4 sheet					
	RM x x	42				
b	SST Bolt and nut 1/2" x 2 " - 16 pcs					
	RM x x	42				
6.9	Labour and material to new hatch cover at forward deck					
	RM x mh	41				
	Material :					
b	Deck Inspection Hatch round dia 8" - 4 sets					
	RM x x	42				
7	**STAND DECK AWNING AND CANVAS**					
7.1	Labour and material to remove, renew and reinstall canvas awning main deck.					
	RM x mh	41				
	Material :-					
a	Black canva awning 210" x 58" - 1 sheet					
	RM x x	42				
b	Nylon rope 9mm - 20 meter					
	RM x x	42				
7.2	Labour to grinding to smooth before painting stand deck awning. (min. charge 10m²)					
	RM x m2	3.6(a)				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
7.3	Fresh water clean transom stand deck awning before painting (min.charge 10m²)					
	RM x m2	3.2				
7.4	Labour and material to spray paint stand deck awning. (min. charge 10m²)(2 coats)					
	RM x x coat	3.13(a)				
	Material;					
a	Hempadur Red - 2 liter					
	RM x x	42				
b	Hemple paint black color - 2 liters					
	RM x x	42				
7.5	Labour and material to remove, renew and install complete black canvas for main console panel					
	RM x mh	41				
	Material :					
a	Black canvas cover 0.8m x 1.5m - 1 sheet					
	RM x x	42				
8	**MOUNTING GPMG**					
8.1	Labour and material to repair mounting gpmg					
	RM x mh	41				
	Material;					
a	SST Bolt Nut - 9 pcs					
	RM x x	42				
b	Fibreglass matt - 5kg					
	RM x x	42				
c	Fibreglass resin - 10kg					
	RM x x	42				
d	Hardener - 0.1kg					
	RM x x	42				
8.2	Labour to grinding to smooth mounting GPMG before painting (min. charge 10m²)					
	RM x m2	3.6(a)				
8.3	Labour and material to repaint mounting GPMG (min. charge 10m²)(2 coats)					
	RM x x m2	3.13(a)				
	Material;					
a	Hemple paint undercoat - 1 liter					
	RM x x	42				
b	Hemple paint black color - 1 liter					
	RM x x	42				
9	**FUEL TANK - 1000 LITER**					
9.1	Labour to pump out fuel from the fuel tank before cleaning.					
	RM x mh	41				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
9.2	Labour to remove floor board and refitting on completion.					
	RM x mh	41				
	Material :					
a	Repair kit - 4 tubes					
	RM x x	42				
9.3	Labour to remove the fuel tank bracket bolt and nuts, hoses, piping in the way of tank removal and fitting back after completion					
	RM x mh	41				
9.4	Labour and material to remove, fabricate and reinstall fuel tank.					
	RM x mh	41				
	Material :					
a	SST plate 3mm - 12m²					
	RM x m2	5.1				
b	SST plate 9mm - 3m2					
	RM x m2	5.1				
c	SST welding rod - 6kg					
	RM x x	42				
d	Argon gas - 2 cylds					
	RM x x	42				
e	SST bolt and nut 1/2" x 2" - 24 pcs					
	RM x x	42				
9.5	Manhole cover and renew oil resisten gasket					
	RM x set	15.5.2				
9.6	Labour to carry out pressure test on tanks. (Min. charge 5m³)					
	RM x m³	15.4				
9.10	Labour and material to renew and reistall inlet hose, overflow hose and oil level hose fuel tank port and stbd.					
	RM x mh	41				
	Material:					
a	SST stop valve 50mm - 2 pcs					
	RM x x	42				
b	SST Nipple - 2 Pcs					
	RM x x	42				
c	Fuel Hose Dia 50mm - 2 Length					
	RM x x	42				
d	SST hose clamp dia 50mm – 4 pcs					
	RM x x	42				
9.11	Labour and material to renew fuel hose from fuel tank to water separator filter engine port and stbd.					
	RM x mh	41				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
	Material:					
a	UNIGAWA Fuel hose 12mm x 7' - 12 meter					
	RM x x	42				
b	SST hose clamp 15mm - 18pcs					
	RM x x	42				
10	**BILGES SECTION (10m²)**					
10.1	Labour to clean bilges forward deck, after deck console panel and fuel tank compartment. (min.charge 10m²)					
	RM x m2	36.1				
10.2	Labour to painting scheme bilge section. (min.charge 10m²)					
	RM x x	3.13(b)				
	Material:					
a	Hemple finish coat - 1 tin					
	RM x x	42				
10.3	Labour and material to dismantle and install new bilges pump.					
	RM x mh	41				
	Material :					
a	Bilge pump - 1 set					
	RM x x	42				
b	Spring Hose 1" - 12 Mtrs					
	RM x x	42				
c	SST Clamp 30mm - 8 Pcs					
	RM x x	42				
d	Seaflo Bilgest Pump Switch 3 Ways - 1 pcs					
	RM x x	42				
10.4	Labour and materials to remove, renew and reinstall manual hand pump.					
	RM x mh	41				
	Materials:					
a	Whale manual Hand pump 38mm - 2 set					
	RM x x	42				
b	Hose spring 1 1/2" - 2 Mtr					
	RM x x	42				
c	SST hose clamp dia 50mm - 4 pcs					
	RM x x	42				
11	**ELECTRICAL AND WIRING SYSTEM**					
11.1	Labour and material to check, renew and install wiring (cabel 2.0mm - 60m)					
	RM x m	40.1				
	Material :					
a	Marine cable type 2.0mm - 60 meters					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
b	Anchor light - 1 set					
	RM x x	42				
c	Stern light - 1 unit					
	RM x x	42				
d	Masthead light - 1 unit					
	RM x x	42				
e	6 gang Switch panel with fuse - 1 set					
	RM x x	42				
f	USB plug 12v - 1 set					
	RM x x	42				
11.2	Labour and material to new wiring for spot light and install spot light.(Cable 2.5mm - 30meters)					
	RM x mtr	40.1				
	Material :					
a	Cable 2.5mm - 30 meter					
	RM x x	42				
b	Sport light DC 12V - 5 set					
	RM x x	42				
c	SST Bracket with bolt and nut - 5 pcs					
	RM x x	42				
11.3	Labour and material to remove, renew and reinstall deck light.					
	RM x mh	41				
	Material :					
a	Dome light dia 6" DC 12V - 2 set					
	RM x x	42				
11.4	Labour and material to remove and renew battery and terminal battery engine port and stbd.					
	RM x mh	41				
	Material :					
a	Free Maintanace battery AMARON N150 - 2 unit					
	RM x x	42				
b	Free Maintanace battery AMARON N120 - 1 unit					
	RM x x	42				
c	Terminal Battery - 6 pcs					
	RM x x	42				
d	Battery cable 21mm - 14mtr					
	RM x x	42				
e	Circuit breaker BEP - 3 sets					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
12	**NAVIGATION SYSTEM (GPS/ECHO SOUNDER/RADAR)**					
12.1	Labour and material to remove, renew and install new GPS, Radar, Echo sounder system on board. Functional test will be carry out after works completed					
	RM x x	43				
	Material :					
a	G3 card - 1 set					
	RM x x	42				
b	Garmine GPS complete set with radar and transducer 3 in1 -1 set					
	RM x x	42				
12.2	Labour and material to remove, renew and reinstall Whelen police light complete set.					
	RM x x	43				
	Materials:-					
a	Whelen police light complete set - 1 set					
	RM x x	42				
12.3	Labour and material to remove and renew VHF Radio.					
	RM x x	43				
	Material:					
a	Icom model IC-M304 VHF c/w Power cable and Fold Down Mount Bracket - 1 set					
	RM x x	42				
13	**ENGINE YAMAHA V8 350HP - 2 UNITS**					
13.1	Labour and material to dismantle, remove and reinstall back engine port and stbd.					
	RM x mh	41				
	Material :					
a	Bolt and Nut 3/4" x 6" - 8pcs					
	RM x x	42				
b	Repair kit - 2 tubes					
	RM x x	42				
13.2	Labour and materials to service, install and setting 2 unit engine YAMAHA V8 350HP. Testing and commissioning will carry out after works completed.					
	RM x x	46				
	Material :					
a	Yamalube motor oil 10W40 - 4 botol					
	RM x x	42				
b	Oil filter - 2 pcs					
	RM x x	42				
c	Fuel filter - 2 pcs					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
d	Seal - 2 pc					
	RM x x	42				
e	Yamaha water separator filter - 2 unit					
	RM x x	42				
f	Spark plug NGK LFR6A-11 - 16 pcs					
	RM x x	42				
g	Thermostart assy - 4 pcs					
	RM x x	42				
h	Zinc anode - 2 pcs					
	RM x x	42				
i	Belting - 2 pcs					
	RM x x	42				
j	Pulley tensioner - 2 sets					
	RM x x	42				
k	Dipstick lub oil engine - 2 pcs					
	RM x x	42				
l	Flywheel - 2 unit					
	RM x x	42				
m	Primer bulb - 2 pcs					
	RM x x	42				
13.3	Labour and material to remove, renew and install high and low pump engine port and stbd					
	RM x x	43				
	Material :					
a	Fuel pump comp 6AW-13907-11 - 2 unit					
	RM x x	42				
b	Fuel pump assy 6CB-24410-01 - 2 unit					
	RM x x	42				
13.4	Labour and material to remove, renew and reinstall gearcase port.					
	RM x x	46				
	Material :					
a	Gearcase CXXL 30 inch - 1 unit					
	RM x x	42				
14	**ENGINE GUARD RAIL**					
14.1	Labour and material to fabricate new and install engine guard rail.					
	RM x mh	41				
	Material :					
a	SST pipe 50mm - 12 meters					
	RM x mtr	19.1				
b	SST elbow 50mm - 4 pcs					
	RM x pcs	19.2				
c	SST bracket 0.1m - 8 pcs					
	RM x pcs	5.3.1				
d	SST bolt and nut 1/2" x 3" - 16 pcs					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**

SKOP KERJA PENYELENGGARAAN/PEMBAIKAN TAHUNAN
BOT RONDA RH 47 PPM SEMPORNA W4 SABAH TAHUN 2026

SER NO.	PESANAN KERJA (DESCRIPTION OF WORK)	TARIFF REF NO	TARIFF COST	MAN HOURS	MATERIAL COST	SUB TOTAL AMOUNT
e	Repair kit- 4 set					
	RM x x	42				
14.2	Labour and material to paint engine guard rail 2 coat paint by spray. (min. charge 10m²)(2 coats)					
	RM x x coat	3.13 (a)				
	Material :					
a	Hempadur Red - 2 liter					
	RM x x	42				
b	Hempathene Black - 2 liter					
	RM x x	42				
c	Hempel Thinner - 0.5 liter					
	RM x x	42				
15	**SUPPLY ONBOARD**					
15.1	Labour and materials to renewal and reinstallation boat accessories on board.					
	Material:					
a	Fire Extingusher 2 Kgs ABC - 2 Units					
	RM x x	42				
b	Fire Extingusher 2 Kgs CO2 - 1 Unit					
	RM x X	42				
c	Fender F3 - 4 pcs					
	RM x x	42				
d	Japan rope soft type 16mm - 60m					
	RM x x	42				
e	Bot Hook- 1 pcs					
	RM x x	42				
f	Ring Buoy - 2 pcs					
	RM x x	42				
g	First aid kit - 1 set					
	RM x x	42				
h	Binacolar - 1 set					
	RM x x	42				
i	Life jacket LALIZAS - 5 pcs					
	RM x x	42				
j	Portable Search Light - 1 set					
	RM x x	42				
k	Tool box Licota 143 Pcs - 1 set					
	RM x x	42				
	SUB-TOTAL		**0.00**	**0.00**	**0.00**	**0.00**
	TOTAL KESELURUHAN		**0.00**	**0.00**	**0.00**	**0.00**